BRUHAT BANGALORE MAHANAGAR PALIKE

Project Division, Yelahanka Zone

SCHEDULE - B

Improvements to roads and drains at Kogilu Layout, Ambedkar Colony surrounding area in Ward No.05

SNo	Quantity	Item Name	Unit	Approved Rates of Sri. M Sudarshan Raju (MSJathin Infra Pvt Ltd.,)	
				In figures	In words
1	347.60	KSRRB M200-13.1. Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications. II. By Mechanical Means. A. Cement Concrete Grade M-15 & M-20. MORTH Specification No. 202. (P.No. 139, I.No. 18.20 of CSR 2018-19)	Cum	526.00	Rupees Five Hundred Twenty Six Only
2	963.60	KSRRB M300-14. Excavation for roadwork in all types of soil by mechanical means including cutting and loading to tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transportation with a lead of 1.00 km and complete as per specifications. MORTH Specification No.301 (P.No.143, I.No.19.14 of PW,P&IWTD S.R 2018-19)	Cum	135.00	Rupees One Hundred Thirty Five Only
3	897.24	KSRB 2-2 : Earthwork excavation by manual means for foundation of buildings, water supply and sanitary lines and electrical conduits etc, either in pits or in trenches 1.5m and above in width, in soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. including breaking of clods complete as per pecifications.(P.No. 7, I.No. 2.3 of CSR 2018-19)	Cum	425.00	Rupees Four Hundred Twenty Five Only
4	60.75	KSRB 4-1.2 : Providing and laying in position plain cement concrete of Mix 1:3:6 with OPC @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM curing complete as per specifications. Specification No. KBS 4.1, 4.2 (P.No.13, I.No.4.2 of PW, P&IWTD SR 2018-19)	Cum	5780.00	Rupees Five Thousand Seven Hundred Eighty Only
5	76.95	Providing laying plain/ reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. With 20mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregates at 0.43cum machine mixed, well compacted for walls and bottom including centring, shuttering, cost of materials, HOM of machinery, curing etc., complete excluding cost of steel as per MORTH specification No. 1500, 1700, 2200. including cost of materials, labour, HOM complete as per specification 15cm wall and bottom thickness (P.No.275, I.No.37.59.2 of PW, P&IWTD SR 2018-19)	Cum	7423.00	Rupees Seven Thousand Four Hundred Twenty Three Only

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

For MSJATHIN INFRA PRIVATE LIMITED

Contractor / Authorised Signatory

Executive Engineer
Project Division
Yelahanka Zone

	Quantity	Item Name	Unit	Approved Rates of Sri. M Sudarshan Raju (MSJathin Infra Pvt Ltd.,)	
				In figures	In words
6	63.00	34.17 Providing and laying in position plain/Reinforced cement cement concrete M20 for sub structure/Superstructure works, with cement @ 320 kgs, 20 mm & down size graded granite metal coarse aggregate @ 0.69 cum and fine aggregates @ 0.46 cum machine mixed with super plasticisers @ 3 lts confirming to IS 9103-2008,concrete laid in layers, well compacted and providing weep holes wherever necessary. with necessary scaffolding, form work etc., including cost of labour, HOM curing etc., complete. (P.No.257, I.No.34.17 of PW, P&IWTD SR 2018-19)	Cum	5541.00	Rupees Five Thousand Five Hundred Forty One Only
7	42.00	KSRB 4-6.1: Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for foundations, footings, bases of columns for mass concrete including cost of all materials, labour complete as per specifications. Specifcation No. KBS 4.6.1 (P.No.16, I.No.4.28 of PW,P&IWTD SR 2018-19)	Sqm	287.00	Rupees Two Hundred Eighty Seven Only
8	378.00	KSRB 4-6.4: Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surfaces such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications. Specification No.KBS 4.6.2 (P.No.16, I.No.4.31 of PW,P&IWTD SR 2018-19)	Sqm	398.00	Rupees Three Hundred Ninety Eight Only
9	10.37	KSRRB M2200-6. Providing T.M.T. steel reinforcement for R.C.C. work including straightening, cutting, bending, hooking, placing in position, lapping and/or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per disign (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM complete as per specification. MORTH Specification No.1600 & 2200.TMT Bars Fe 500 (P.No.18, I.No.4.46.2 of PW, P&IWTD SR 2018-19)	MT	78978.00	Rupees Seventy Eight Thousand Nine Hundred Seventy Eight Only
10	171.00	Providing and fixing RCC Precast cover slab of 100mm thick for drain in cement concrete M20 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge. (Data Rate)	Sqm	2454.00	Rupees Two Thousand Four Hundred Fifty Four Only
11	126.00	Providing and fixing RCC Precast cover slab of 250mm thick for drain in cement concrete M20 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge. (Data Rate)	Sqm	5688.00	Rupees Five Thousand Six Hundred Eighty Eight Only
12	550.00	KSRB12-2 : Providing and laying in position plain cement concrete M7.5 using 40mm and down size graded granite metal, machine mixed concrete laid in layers not exceeding 15 cms thick, well compacted, for internal diameter stoneware pipes including cost of materials, labour charges, HOM curing complete as per specifications Specification No. KBS 4.1 / 4.2(I.No. 11.15 of CSR 2018-19)-300mm Dia Pipe	M	647.00	Rupees Six Hundred Forty Seven Only
13	550.00	KSRB 12-1 : Providing and laying in position to required level or slope of internal diameter salt glazed stoneware pipes grade A and jointing with stiff mixture of cement mortar in proportion of 1:1, testing of pipes and joints,including cost of materials, labour charges complete as per specifications. Specification No. KBS 12.2.5 / 12.7-(I.No. 11.6 of CSR 2018-19)300mm Dia Pipe	M	702.00	Rupees Seven Hundred Two Only

For MS JATHIN INFRA PRIVATE LIMITED

Contractor

Authorised Signatory

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

	Quantity	Item Name	Unit	Approved Rates of Sri. M Sudarshan Raju (MSJathin Infra Pvt Ltd.,)	
				In figures	In words
14	21.00	KSRB 12-5 : Constructing brick masonry circular type manhole 1.22 m internal dia at bottom and 0.56m dia at top, with table moulded and non modular bricks of class designation 50 in cement mortar 1:4, inside cement plaster 12mm thick with ement mortar 1:3, finished with a floating coat of neat cement, foundation concrete M 10 using 40mm and down size granite metal and making necessary channel in cement concrete M 15 with 20mm and down size granite metal, finished with a floating coat of neat cement, with S.F.R.C. cover and frame (heavy duty, HD-20 grade designation) 560mm internal diameter confirming to IS :12592, total weight length of cover and frame to be not less than 182 kg, fixed in cement concrete M 15 20mm and down size broken granite metal, providing and removing centering, shuttering including cost of materials, labour charges, HOM complete as per specifications. (Excavation, footrests and 12mm thick cement plaster on the external surface shall be paid separately) Specification No. KBS 12.4 (I.No. 11.39 of CSR 2018-19)-1.22m Diamanhole and 1.68m Depth	No	32628.00	Rupees Thirty Two Thousand Six Hundred Twenty Eight Only
15	715.69	KSRB 2-4 : Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m. and lift upto 1.5 m. including cost of all labour complete as per specifications. (P.No.6, I.No.2.11 of PW,P&IWTD SR 2018-19)	Cum	111.00	Rupees One Hundred Eleven Only
16	907.60	KSRRB M300-53. Construction of embankment with approved material Gravel/Murrum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement Table 300-2 complete as per specifications, including cost of gravel / murrum, watering charges & compaction by vibratory roller to 95% of modified proctors density. MORTH Specification No. 305. (P.No.147, I.No.19.60 of PW,P&IWTD SR 2018-19)	Cum	362.00	Rupees Three Hundred Sixty Two Only
17	165.00	KSRB 2.6 : Providing and filling sand in foundation to required depth for sub soil treatment including watering ramming with all lead and lift complete as per specifications. specification. No. KBS 2.10.2. (P.No.7, I.No.2.13 of PW,P&IWTD SR 2018-19)	cum	2293.00	Rupees Two Thousand Two Hundred Ninety Three Only
18	82.50	Construction of granular sub-base Grading-V as Sub-base and drainage layer by providing coarse graded crushed stone aggregates of granite/trap/basalt material, mixing by mix in place method by rotavator at OMC,spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the 98 % proctor density, complete as per specifications. Clause 401 of MORTH V Revision.. (P.No.153, I.No.20.6 of PW,P&IWTD SR 2018-19)	Cum	1948.00	Rupees One Thousand Nine Hundred Forty Eight Only
19	110.00	KSRRB M 400-17, Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechaniqal mix plant carriage ' of mixed Material by tipper to site, laying in uniform layers with paver in sub- base/ base course on well prepared surface and compacting with vibratory roller to achieve the desired density.complete as per specifications. MORTH Specification No. 406 (P.No.155, I.No.20.18 of PW,P&IWTD SR 2018-19)	Cum	2101.00	Rupees Two Thousand One Hundred One Only

For MS JATHIN INFRA PRIVATE LIMITED

Contractor

Authorised Signatory

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

13/8/20

	Quantity	Item Name	Unit	Approved Rates of Sri. M Sudarshan Raju (MSJathin Infra Pvt Ltd.,)	
				In figures	In words
20	260.85	KSRRB M600-1. Construction of dry lean cement concrete mix CC1:5:10 with OPC cement @160Kgs, with 25mm and down size graded granite metal coarse aggregate at 0.86cum and fine aggregates @ 0.58cum Sub- base over a prepared sub-grade with (coarse and fine aggregate conforming to IS: 383) aggregate cement ratio not to exceed 15:1. Aggregate gradation after blending to be as per Table 600-1, cement content not to be less than 160 kg/ cum, optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 Mpa at 7 days, mixed in a batching plant, transported to site, laid with a compacting with 8-10 tonnes vibratory roller, finishing and curing complete as per specifications. . MORTH V Revision Specification No. 601, IS 456 Table-5. with OPC at 150 kg/cum and coarse aggregate 0.86cum, fine aggregate 0.58cum using Concrete Batch mix Plant at 75 cum/hr capacity with Slip.((P.No.174, I.No.22.1.1 of PW,P&IWTD SR 2018-19)	Cum	3990.00	Rupees Three Thousand Nine Hundred Ninety Only
21	260.85	Constructing un-reinforced, plain cement concrete for pavements using Grade concrete M30 over a prepared base with OPC coarse aggregate at 0.69 cum, fine aggregates at 0.46 cum,Coarse and fine aggregate conforming to IS:383-2016, with Superplastizer at 3 lts conforming to IS 9103-2008. mixed in a concrete mixer of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work as per drawing). & Spreading the concrete with shovels, rackers compacted using needle, screed and plate vibrator and finished with floaters in a continuous operation including provision of contraction, expansion, construction and longitudinal joints,including groove cutting charges, joint filler, separation membrane of impermiable plastic sheet of 125 micron, sealant primer, joint sealant, admixtures as approved, curing compound, finishing to lines and grades, textured with texturing machine, and curing including cost of all materials, labour,hire charges of machineries,all lead & lift charges etc., complete as per	Cum	5471.00	Rupees Five Thousand Four Hundred Seventy One Only
22	1739.00	Vaccum de-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator, HOM of machinery, Screed Vibratory, Power Floater, blade and disc etc., with all lead and lift. (P.No 176, I.No.22.7 of PW,P&IWTD S.R 2018-19)	Sqm	74.50	Rupees Seventy Four And Paise Fifty Only
23		GST @ 12%			

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92
19/8/20

For MSJATHIN INFRA PRIVATE LIMITED

Authorised Signatory

Contractor

Executive Engineer
Project Division
Yelahanka Zone